

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1974


15-155-01604-0000

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

_____ Reno _____ County. Sec. II Twp. 26 Rge. 6 W (E) _____ (W)
Location as "NE/CNWSW" or footage from lines. C NE SE SW
Lease Owner A. Scott Ritchie
Lease Name Sohrag "R" Well No. I
Office Address Bx 165 Lyons, Kansas 67554
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 4- 20 1963
Application for plugging filed _____ 7- 10 1974
Application for plugging approved _____ 7- 11 1974
Plugging commenced _____ 7- 29 1974
Plugging completed _____ 7- 31 1974
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3997'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,962'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3600'. Dumped 5 bx of cement. Mudded hole to 248'. Made 13' of rock bridge. Dumped 25 bx cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 bx of cement, filling to the bottom of the collar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

Subscribed and sworn to before me this 31st day of July, 1974

My commission expires December 31, 1977

[Signature] Notary Public.

GROUP EXPLORATION COMPANY
Sterling, Kansas

15-55-01604-0000

WELL LOG - - - - - Schrag "B" #1
Located: C NE SE SW Section 11-26N-6W, Reno County, Kansas.

OWNER: A. Scott Ritchie
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 4-8-63
COMPLETED: 4-20-63

ROTARY TOTAL DEPTH: 3997'

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1 1974
CONSERVATION DIVISION
Wichita, Kansas

LOG

0 - 935	Shale & Shells	
935 - 1215	Lime & Shale	
1215 - 1350	Lime	
1350 - 1535	Shale & Lime	
1535 - 1578	Lime & Flint	
1578 - 1740	Lime	
1740 - 2425	Shale & Lime	
2425 - 2680	Lime	
2680 - 2895	Shale & Lime	
2895 - 3395	Lime	
3395 - 3613	Shale & Lime	
3613 - 3625	Miss. Chert	
3625 - 3780	Miss. Lime	
3780 - 3792	Chert	
3792 - 3840	Lime & Shale	
3840 - 3997	Shale	T.D.

CASING RECORD

Set 8 5/8" Surface Casing @ 248' K.B.
with 175 sacks HA-5 Pozmix.

Ran 5 1/2" casing @ 3996' with 150 sacks
60 x 40 Pozmix salt saturated, with 10
bbl. of Brine ahead of plug.