

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21455-00-00  
Spot: S2SESE Sec/Twnshp/Rge: 21-26S-9W  
330 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: COLE Well Number: 1-21  
County: RENO Total Vertical Depth: 4214 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N. LOGAN PO BOX 195  
ATTICA, KS 67009

Production Casing Size: 4.5 feet: 3633 125 SX CMT  
Surface Casing Size: 8.625 feet: 239 250 SX CMT **8936 96**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2003 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RANDY NEWBERRY Company: R & B OIL AND GAS, INC. Phone: (620) 254-7251

Proposed Plugging Method: Sand bottom to 3400' and 4 sacks; 1350' and 35 sacks; 800' and 35 sacks; 300' to 0'.

RECEIVED  
KCC DISTRICT #2  
JUL 9 2003  
7-9-03  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/08/2003 3:00 PM KCC Agent: JACK LUTHI

**Actual Plugging Report:**

Sanded the bottom to 3400' and 4 sacks of common. Shot 4-1/2" casing off at 2415'. Pulled to 1350' and pumped 35 sacks. Pulled to 800' and 35 sacks. Pulled to 300' and circulated cement to surface.

Remarks: ALLIED TICKET #12487 60/40 4%

Plugged through: CSG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED

DATE 7.23.03

INV. NO. 2004060091