

2-100616

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-155-21,141.0000

C W/2 W/2 SE, SECTION 2 TOWNSHIP 26 RANGE 10W

OPERATOR LICENSE # 3067 1320 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR Molitor Oil, Inc.
NAME & RR #1, Box 74
ADDRESS Spivey, KS 67142

LEASE NAME: Compton #1
COUNTY: Reno / 128.37
WELL TOTAL DEPTH: 3950'
CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 184'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD _____ D&A X
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Duke Drilling Co., Inc.
ADDRESS: Great Bend, KS LICENSE: 5929

COMPANY TO PLUG AT: HOUR: 4:00p DAY: 8 MONTH: 8 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: John Ambuster
COMPANY NAME: Duke Drilling Co., Inc. PHONE: _____

WERE: 35 sx 1450' - 35 sx 1000' - 35 sx 230' - 25 sx 60' -
10 sx R.H. - 10 sx M.H.

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (_____) NONE (X)

COMPLETED: HOUR: 5:00p DAY: 8 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:

Fill hole w/mud to 1450' - spott 35 sx cmt - pull
pipe to 1000' - spot 35 sx cmt - pull pipe to 230' -
spot 30 sx cmt - pull pipe to 60' - circ 25 sx cmt to
surf - put 10 sx in mouse hole & 15 sx in rat hole.

REMARKS: Howco #00055 60/40 3% gel

I DID NOT OBSERVE THIS PLUGGING.

J. L. Sanders
J. L. Sanders (AGENT)

*Rec'd 8-17-90
KCC*

INVOICED

DATE: 8-24-90

INV. NO. 29077

DL