

2-070681

2-14

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-21,229-0000

SE NE NE, SECTION 10 TOWNSHIP 26 RANGE 10W

OPERATOR LICENSE # 5122 4290 FEET FROM S SECTION LINE
OPERATOR IANNITTE OIL COMPANY 330 FEET FROM E SECTION LINE
NAME & P.O. BOX 308
ADDRESS GREAT BEND, KS 67530

LEASE NAME: DETERDING #1
COUNTY: RENO
WELL TOTAL DEPTH: 4050' 131.62
PIPE: 5 1/2" @ 4043'
SURFACE CASING: 8 5/8" @ 212'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 14 MONTH: 2 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 654-8170

WERE: SAND TO 3850' AND 5 SACKS

35 SACKS AT 1500'

35 SACKS AT 950'

300'- 0'

RECEIVED

KANSAS CORPORATION COMMISSION

2-19-97 FEB 19 1997

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI CONSERVATION DIVISION

WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { X } PART { } NONE { }

COMPLETED: HOUR: 6:00 DAY: 14 MONTH: 2 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3850' AND 5 SACKS. SHOT 5 1/2" CASING OFF AT 2200'.

PULLED TO 1500', PUMPED 35 SACKS. PULLED TO 950, PUMPED 35 SACKS. PULLED TO 300',

CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #4209

INVOICED

DATE 2-19-97

INV. NO. 47601

2-14

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

FORM CP-2/3

REV. 3/90