

To: 1 051703
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-30 API NUMBER 15-
SW NE SW, SEC. 5, T 27 S, R 20 W/8
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5144
Operator: Mull Drilling Company, Inc.
Name & Address: P.O. Box 2758
Wichita, KS 67201

Lease Name Einsel J Well # 1
County Kiowa 157.62
Well Total Depth 4850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 531

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 30 Month: 7 Year: 19 93

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pullers (phone) 316-938-2943

work: 4 1/2" at 4842' w/125 sx cement, Open hole 4842-50'. Perfs at 4820-40'
1st plug sand back to 4775' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 30 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4780' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE: 8-12-93

INV. NO. 38321

Signed Richard W. [Signature] (TECHNICIAN)
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
AUG - 9 1993