

1:060367

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,590-B

C SE SE , SEC. 29 , T 27 S, R 19 W
660 N SE Corner of
feet from N/S section line
660 W SE Corner of
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Lease Name Stevens B Well # 1

Operator: TGT Petroleum Corp.

County Kiowa

Name & Address 209 East William

Well Total Depth 4989 162' 14" feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 481

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 14 Month: October Year: 19 84

Plugging proposal received from Harvey Moore

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1220' with 50 sx cement

2nd plug at 610' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plug water well with 5 sx Plugging Proposal Received by Paul G. Luthie
cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:15 pm Day: 14 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1220' with 50 sx cement, 2nd plug at 610' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement, and plugged water well with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

10-17-84 OCT 17 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed Paul G. Luthie
(TECHNICIAN)

DATE 10-18-84

INV. NO. 4409 10-14

NOV 19 1984