

1091064

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,195-0000  
NW NE NW SEC. 27, T 27 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 4720 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3800 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BRENSING "B" WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA

158.44

OPERATOR LICENSE # 5118

WELL TOTAL DEPTH 4875 FEET

OPERATOR: TGT PETROLEUM CORP.

PRODUCTION CSG: SIZE 5 1/2" @ 4874' WITH 200 SX

NAME AND ADDRESS 7570 W 21ST BLDG 1010 D WICHITA, KS 67205

SURFACE CASING: SIZE 8 5/8" @ 439' WITH 200 SX

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:40 AM DAY: 14 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM HAROLD BELLERIVE

RECEIVED  
STATE CORPORATION COMMISSION  
STATE CORPORATION COMMISSION  
JUL 24 2000  
7-24-00  
CONSERVATION DIVISION  
C. Wichita, Kansas

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4830-32

1ST PLUG SET CIBP @ 4700' WITH 2 SX CEMENT. 2ND PLUG PUMP 15 SX GEL AND 50 SX CEMENT AT 1250'. 3RD PLUG PULL TO 470' SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' CIRCULATE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:35 AM DAY: 14 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLIG SET CIBP AT 4700' WITH 2 SX CEMENT. 2ND PLUG PUMP 15 SX GEL & 50 SX CEMENT AT 1250'. 3RD PLUG PULL TO 470'. SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' CIRCULATE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3000' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING

INVOICED

DATE 7/25/00

SIGNED

[Signature]

(TECHNICIAN)

FORM CP-2/3

NW, NE, 1060/24

[Handwritten initials]