

5-6-88

To: 1 061103  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 165' E NE NE NE SEC. 21, T 27 S, R 19 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,3800000  
4950 feet from S section line  
165 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061  
Operator: Oil Producers Inc. of Kansas  
Name &  
Address P.O. Box 8647  
Wichita, KS 67208

Lease Name Barnes Well # 1  
County Kiowa 155.68  
Well Total Depth 4790 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 580

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 5:30 p.m. Day: 6 Month: 5 Year: 19 88

Plugging proposal received from James Rockhold  
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4790' PBD 4710' Perfs at 4181-89, 4213-21, 4345-49'  
1st plug sand back to 4130' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 p.m. Day: 6 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released  
8 5/8" wiper plug and pumped 130 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 500 psi. and shut in 100 psi.

5-13-88  
MAY 13 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3100' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-17-88  
INV. NO. 20648

(If necessary) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas