

15-097-30001-0000

To: 1 090737
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud date 12/31/64
C SE SW, SEC. 21, T 27 S, R 20 W/E
660 feet from S section line
3300 feet from E section line

10-25
TECHNICIAN'S PLUGGING REPORT
Operator License # 5144
Operator: Mull Drilling Company Inc.
Name & Address: P.O. Box 2758
Wichita, KS 67201

Lease Name Zeigler Well # 2
County Kiowa 158.82
Well Total Depth 4887 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 552

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co., Inc. License Number _____
Address P.O. Box 368, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:45 a.m. Day: 4 Month: 10 Year: 19 96

Plugging proposal received from Mike Meyers
(company name) Mull Drilling Co. Inc. (phone) 316-264-6366

Work: 4 1/2" at 4861' w/125 sx cement, Open hole 4861-87'
Casing collapsed at 3940'. Attempted to mill casing back open and went outside pipe. Also
have 947' of tubing and rods in hole. Casing parted and tubing & rods top at 3940'.
Pump 100 sx cement from 4887-3700', gel from 3700-1300', 75 sx cement from 1300' to surface.
Pump 150 sx cement down surface casing annulus.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 25 Month: 10 Year: 19 96

10/4/96
ACTUAL PLUGGING REPORT 1st plug pumped 100 sx cement, 20 sx gel, and 75 sx cement down 4 1/2"
casing. Maximum pressure 300 psi and shut in 100 psi.

2nd plug hooked onto backside and pumped 35 sx cement. Blew hole in surface casing at 200 psi.
10/25/96 Perforated casing at 511' from surface. Pumped down 4 1/2" with 85 sx cement-25' out
perfs, 60 inside 4 1/2".

Backside filled from 125' to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

INVOICED

(If additional description is necessary, use back of this form.)

I (did ~~XXXXXX~~) observe this plugging.
DATE Oct 29 1996

10-28-96
Signed _____
(TECHNICIAN)

INV. NO. 46851
10-25