

1091030

TO: STATE CORPORATION COMMISSION API NUMBER 15-097-21,263-0000
E/2 SE NE SEC. 16, T 27 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 360 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BRENSING WELL # 1-16

TECHNICIAN'S PLUGGING REPORT COUNTY KIOWA

OPERATOR LICENSE # 5086 WELL TOTAL DEPTH 4951 FEET

OPERATOR: PINTAIL PETROLEUM LTD. PRODUCTION CSG: SIZE 5 1/2" @ 4951' WITH 100SX

NAME AND ADDRESS 225 N MARKET #300 SURFACE CASING: SIZE 8 5/8" @ 452' WITH SX
WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 22 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4852-4860

1ST PLUG SAND TO 4798' WITH 5 SX CEMENT ON TOP. 2ND PLUG PULL TO 1250' SPOT 6 HULLS, 10 SX GEL, 50 SX CEMENT. 3RD PLUG PULL TO 495' SPOT 5 SX GEL AND 50 SX CEMENT. 4TH PLUG PULL TO 40' SPOT 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:50 PM DAY: 22 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4798' WITH 5 SX CEMENT ON TOP. 2ND PLUG PULL TO 1250' SPOT 6 HULLS, 10 SX GEL, AND 50 SX CEMENT. 3RD PLUG PULL TO 495' SPOT 5 SX GEL AND 50 SX CEMENT. 4TH PLUG PULL TO 40' SPOT WITH 10 SX CEMENT. STAYED FULL:

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2848' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 1/5/00
WV. NO. 061066

Conservation Division
Wichita, Kansas
SIGNER (TECHNICIAN) FORM CP-2/3
R