

To: 1 090751
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-21,356-0000
NW NW SW, SEC. 8, T 27 S, R 20 W/X
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30193
Operator: Brange
Name: _____
Address: 1118 Spruce St.
Pratt, KS 67124-1256

Lease Name Einsel Trust I Well # 1
County Kiowa 158.14
Well Total Depth 4866 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 331

10-31

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 31 Month: 10 Year: 1996

Plugging proposal received from Mike Kelso
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

- Work: 4 1/2" at 4865' w/150 sx cement, PBTD 4864', Perfs at 4856-60'
1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer,
2nd plug at 1300' with 50 sx cement,
3rd plug at 360' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3:50 p.m. Day: 31 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of sand
through bailer, 11-4-96
2nd plug pulled casing to 1300' and spotted 10 sx gel and 50 sx cement,
3rd plug pulled to 350' and spotted 50 sx cement,
4th plug pulled to 40' with 10 sx cement.

RECEIVED
NOV - 11 A 11:52
KANSAS CORP COM

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2850' of 4 1/2" casing.
(If additional description is necessary, use BAGX of this form.)

INVOICED
I (C) d/ ~~XXXXXX~~ observe this plugging.

DATE 11-5-96
INV. NO. 46908

Signed [Signature]
(TECHNICIAN)