

To: 1070009

7-1

API NUMBER 15- 097-20,573-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION App. NW NW NE, SEC. 8, T 27 S, R 20 W/2
130 S. Market, Room 2078
Wichita, KS 67202

510 feet from NXX section line

2030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Einsel Well # G-1

Operator: Oil Producers, Inc. of Kansas

County Kiowa 160.06

Name & Address P.O. Box 8647

Well Total Depth 4925 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 584

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12 p.m. Day: 1 Month: 7 Year: 1997

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4900' w/175 sx cement, PBSD 4891', Perfs at 4840-62'

1st plug sand back to 4790' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 7 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4790' and dumped 5 sx cement on top of sand through bailer,

7-7-97

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2571' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

I (did) observe this plugging.

DATE JUL 16 1997 INV. NO. 48553

Signed [Signature] (TECHNICIAN)

KANSAS RECEIVED PLUGGING SECTION JUL 16 1997