

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20369-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 35-27S-19W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: PYLE Well Number: 1
County: KIOWA Total Vertical Depth: 4900 feet

Operator License No.: 5118 Conductor Pipe: Size _____ feet:
Operator Name: TGT PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 322 WITH 250 SX CMT
Address: 7570 W 21ST ST N. STE1010D Production: Size 5.5 feet: 4899 WITH 100 SX CMT
WICHITA, KS 67275 Liner: Size _____ feet: 159.25

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/01/2000 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: HAROLD BELLERIVE Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS & 5 SX CMT. 1ST PLUG AT 1200' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/01/2000 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:
PERFS AT 4829-31'. SANDED BACK TO 4640' AND PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 2000

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3000' OF 5 1/2" CONSERVATION DIVISION
Wichita, Kansas
Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN) JA

INVOICED

DATE 12/7/00

DEC 04 2000

INV. NO. 2001061

MP