

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20912-00-00
Spot: SENW Sec/Twnshp/Rge: 4-27S-6W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: GRABER Well Number: 1
County: KINGMAN Total Vertical Depth: 4086 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

Production Casing Size: 4.5 feet: 4082 150 SX CMT
Surface Casing Size: 8.625 feet: 292 275 SXC MT **\$132.80**

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2003 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PER KCC RULES AND REGULATIONS.
RECEIVED
KCC DISTRICT #2
AUG 28 2003
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/21/2003 4:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3320' and 4 sacks of common. Shot 4-1/2" casing off at 2700'. Pulled to 1000'. Pumped 35 sacks. Pulled to 500'. Pump 35 sacks. Pulled to 350'. Circulated cement to surface.

Remarks: COPELAND CEMENT 60/40 4%

Plugged through: CSG

District: 02

Signed Jack Luthi
(TECHNICIAN)

INVOICE
DATE 9.9.03
INV. NO. 2004060487