

2 040255

15-095-21010-0000

R 279-S-92

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE14, SEC. 30, T 29 S, R 10 W
330 feet from N/4 section line
1320 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Hageman Well # B-1

Operator: TXO Prod. Corp.

County Kingman 88.40

Name & Address 200 W. Douglas #300

Well Total Depth 2720 feet

Wichita Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Pratt Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Jerry Pritchard

(company name) TXO Prod Corp. (phone) _____

were:

2 3/8 2718 Bot. 10sx to 2232

Perf 2632-39 Top. 3 Hull 15 gel 20sx

Plugging Proposal Received by St. U. S.
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1310 Day: 19 Month: 2 Year: 19 86

ACTUAL PLUGGING REPORT 10 sacks of cement was pumped down the 2 3/8" to 2232'. We let it sit for 1 hour and then pressured up to 1000#. The pressure held, so the 2 3/8" was shot off and recovered from 1835'. The top was squeeze plugged thru the 8 5/8" casing by pumping 3 sacks of hulls, 15 sacks of gel and 150 sacks of cement.

Remarks: Howco 351427 SI 700# Mx 800#

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 27 1986

INV. NO. 12729

WC
2-19

STATE CORPORATION COMMISSION

FEB 26 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed St. U. S.
(TECHNICIAN)

RO

FORM CP-2/3
Rev. 01-84