

3-14

2-040616

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-095-20938-0000

C S/2 SW, SECTION 30 TOWNSHIP 29 RANGE 10W

OPERATOR LICENSE # 3399 1320 FEET FROM S SECTION LINE  
3500 FEET FROM E SECTION LINE

OPERATOR Farrar Pipe & Supply  
NAME & P. O. Box 209  
ADDRESS Medicine Lodge, KS 67104

LEASE NAME: Hageman #1

COUNTY: Kingman 88.72

WELL TOTAL DEPTH: 2730'

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 320' (M-11-11-11)  
STATE CORPORATION COMMISSION

ABANDONED OIL WELL        GAS WELL X INPUT WELL        SWD        D&A         
OTHER WELL AS HEREINAFTER INDICATED:         
4-3-91  
APR 7 1991

PLUGGING CONTRACTOR: Clarke Corporation CONSERVATION DIVISION  
ADDRESS: Medicine Lodge, KS LICENSE: 5105 Wichita, Kansas

COMPANY TO PLUG AT: HOUR:        DAY:        MONTH:        YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Elmo Morganstien  
COMPANY NAME: Clarke Corporation PHONE:       

WERE: 4-1/2" @ 2729'/100 sx - perf 2659'-2661' - sand to  
2500' - 35 sx @ 1500' - 35 sx @ 1100' - circ cmt.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (        ) PART ( X ) NONE (        )

COMPLETED: HOUR: 16:45 DAY: 14 MONTH: 3 YEAR: 1991

ACTUAL PLUGGING REPORT:

Perfs sanded back to 2500' and capped w/5 sx cmt - 4-  
1/2" shot; loose from 2080' and pulled to 1507' and 35  
sx cmt spotted - 4-1/2" pulled to 1107' and 35 sx cmt  
spotted - 4-1/2" pulled to 380' & cmt circ to surface.

REMARKS: 40/60 poz 4% gel B. J. Services #636513

I DID OBSERVE THIS PLUGGING.

**INVOICED**

Steve Van Gieson  
Steve Van Gieson (AGENT)

DATE 4-11-91

INV. NO. 31482