

Corrected on 15-155-21129-00 02. 8/30/02 of JB
Invoice Paid on 2002060993

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21129-00-00
Spot: NENENE Sec/Twnshp/Rge: 11-26S-6W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: H A KREHBIEL Well Number: 1
County: RENO Total Vertical Depth: 4044 feet

Operator License No.: 5808
Op Name: ALLAM, W. R. JR. D/B/A W.R.A. OIL CO.
Address: PO BOX 2325
HUTCHINSON, KS 67504

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 231 125 SX CMT
Production: Size 5.5 feet: 4038 175 SX CMT
Liner: Size feet:

\$ 131.43

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/12/2001 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JOE MONTY Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3200' and 5sxs, 35sxs-900', 35sxs-400', 280'-0.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 11/12/2001 3:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:
Sanded bottom to 3200' and 5sxs shot 5 1/2" casing off at 2530'. Pulled to 900'. Pumped 35sxs pulled to 400' and pumped 35sxs, pulled to 280'. Pumped to surface. 11-13-01 cement fell 56' used 1 yrd of slurry to surface.

RECEIVED
KCC DISTRICT #2
NOV 20 2001
11-20-01
WICHITA, KS

Remarks: UNITED # 3450 60/40
Plugged through: CSG

District: 02

DO NOT COUNT!
INV: Nov 20-01

Signed Jack Luthi
(TECHNICIAN)

INVOICED
DATE 11-27-01
INV. NO. 2002060993