

Form CP-3
Rev. 6-26-62

B

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSIONAUG 12 1965
8-12-65
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Kenneth RuppComplete Address: 1035 Wichita Plaza, Wichita, KansasLease Name Pyle Well No. # 1Location C SW NE Sec. 35 Twp. 27 Rge. 19 (E) (W) WCounty Kiowa Total Depth 5019'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Red Tiger Drilling CompanyAddress: 1720 Wichita Plaza, Wichita, Kansas License No. Operation Completed: Hour 4:00 AM Day 8th Month August Year 1965

The Above well was plugged as follows:

617' of 8 5/8" surface pipe, cement circulated with 425 sacks. Hole was
filled with drilling mud to 300', 1st cementing plug, bridged solid with
dry cement and hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks to
the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-12-65INV. NO. 1616-WSigned: Archie Elving
Well Plugging Supervisor