



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Martin Oil Co

Complete Address 527 Union Center Wichita, KS

Lease Name Pyle Well No. 1

Location C SW/NE Sec. 35 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 4988

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 10:30 AM Day 7 Month 8 Year 1974

The above well was plugged as follows:

617 ft 8 5/8 surface cemented with 150 sacks. 5020 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4784 ft. Sand to 4700 ft, 5 sacks
cement with bailer. Pulled 2835 ft 5 1/2. Set 10 ft rock bridge at
200 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8/9/74
INV. NO. 9689-W