

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill;
filed August 29, 1967.

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Morford Well No. # 1

Location C SW NW Sec. 10 Twp. 29 Rge. 20 (E) (W) W

County Kiowa Total Depth 5193'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Donelson Drilling Company

Address: 290 S. Pershing, Wichita, Kansas License No.

Operation Completed: Hour 12:15 PM Day 23rd Month Sept. Year 1967

The Above well was plugged as follows:

496' of 8 5/8" surface pipe, cement circulated with 250 sacks. 1st cementing
plug and 1 sack of hulls was pushed in fluid to 400', and cemented with 25
sacks, through the drill pipe, with cement from 400' to 325'. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls
on fluid at 40', and cemented with 10 sacks, with cement from 30' to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

STATE CORPORATION COMMISSION

SEP 27 1967

Signed: Archie Elving

Well Plugging Supervisor

INVOICED

DATE 9/27/67CONSERVATION DIVISION
Wichita, KansasINV. NO. 6397-W