

40 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Harvey Rosen 15-155-00123-0000

Complete Address: 5405 East Central, Wichita, Kansas

Lease Name Stucky Well No. 11

Location SW SW SW Sec. 14 Twp. 26 Rge. 6 (E) (W) X

County Reno Total Depth 4200'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 5:30 PM Day 13 Month November Year 1963

The Above well was plugged as follows:

5 1/2" plug pushed to 3610'. Hole filled with sand to 3600' and cemented
with 5 sacks. Hole filled with mud to 260'. Rock bridge set from 260'
to 250' and hole cemented with 25 sacks. Hole filled with mud to 30'.
Rock bridge set from 30' to 20' and hole cemented to base of cellar with
10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/18/63

INV. NO. 8116-w