

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 16 1967

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed May 31, 1967.

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Ks. 67202

Lease Name: Einsel "G" Well No. # 1

Location: C SE NW Sec. 20 Twp. 27 Rge. 20(E)(W) W

County Kiowa Total Depth 4970' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

369' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill hole with drilling mud to 350', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent