

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-097-20033-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed August 29, 1967.

Dear Sir:

Mr. Joe Butts of Mull Drilling Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Butts guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Morford Well No. # 1

Location: C SW NW Sec. 10 Twp. 29 Rge. 20 (E)(W) W

County Kiowa Total Depth 5193' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Butts was instructed to plug the well as follows:

496' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill  
hole with drilling mud to 400', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1967

Very truly yours,

Arlene Elving  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas