



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-07128-0000 September 21, 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1964

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: V. E. Wiggins

Complete Address: Box 191, Mc Pherson, Kansas

Lease Name: J. Graber Well No. 1

Location: C W 1/2 NW NE Sec. 14 Twp. 26 Rge. 6 (X) (W) X

County Reno Total Depth 3999' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3600' and cement with 5 sacks.

Fill hole with mud to 250'. Set rock bridge from 250'

to 240' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,

William J. Lawrence
Conservation Division Agent