

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, KS 67601

PHONE# (913) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (XCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	449'	none
				4 1/2	4600'	2425'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each side. Sanded bottom to 3345' & ran 4 sks cement. Shot at 3017', worked pipe. Shot at 2721', worked pipe. Shot at 2425', worked pipe free. Pulled to 1072', pumped 10 sks gel, 50 sks cement, displaced with 5 sks gel water to 1075'. Pulled to 530', pumped 50 sks cement. Pulled to 100', circulated 30 sks cement to surface. Pulled rest of csq. Plugging complete. 60/40 poz 16% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 552

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 97

Diane Stenberg
Notary Public

My Commission Expires:



RECEIVED
KANSAS CORP. COMM.
1997 MAR 19
A 11:24