

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-02-3-117
15-097-20875-0000

API NUMBER Drilled 4/82

LEASE NAME Kelton

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 27S RGE. 16W (E) or (W)

COUNTY Kiowa

Date Well Completed

Plugging Commenced 3-5-97

Plugging Completed 3-7-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, KS 67601

PHONE (913) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)
by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	493'	none
				5 1/2	4549'	3002'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each side. Sanded off bottom to 3969' & ran 5 sks cement. Shot at 3219' worked pipe. Shot @ 3002' worked pipe free. Pulled to 1050', pumped 50 sks cement. Pulled to 520', pumped 50 sks cement. Pulled rest of csg and topped with 35 sks cement. Plugging complete. 60/40 poz 6% gel. 3/12/97 Topped off with another 50 sks cement.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 15

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 97

Jane Stenberg
Notary Public

My Commission Expires:



Form CP
Revised 05-

RECEIVED
KANSAS CORP COM
997 MAR 19
A 11:24