


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 4 Twp. 27 Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NE SW
Lease Owner J. Mark Richardson
Lease Name French "B" #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/3/80 _____ 19____
Plugging completed 1/8/80 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____
If a producing well is abandoned, date of last production
_____ 19____
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owans
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4525
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	475	none
				4 1/2"	4515	3450

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4475' and ran 4 sacks cement. Shot pipe at 3610', 3515', 3420', pulled 106 joints. Squeezed hole with 4 sacks hulls, 25 sacks gel, 4 sacks hulls. Released plug and displaced with 150 sacks 50-50 pozmix, 1% gel and 3% cc.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

1-14-80

JAN 14 1980

(If additional description is necessary, use BACK to _____ sheet)


Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of Jan., 19 80

My commission expires _____



Margaret Melcher
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

French #1
 NW-NE-SW Sec 4-27S-16W
 Kiowa County Kansas

Commenced: 11-27-76

Completed: 12-9-76

OPERATOR: J. MARK RICHARDSON

From	Depth to	Formation	Remarks
0	185	Sand	
185	300	Sand-Shale	
300	485	Redbed	Ran 12 jts of 28# 8 5/8 csg set @ 478' Cemented w/
485	740	Redbed-Shale	475 sks Common 3% CC
740	1615	Shale-Shells	PD @ 2:30 a.m. 11-28-76
1615	2095	Shale	
2095	2195	Shale-Lime	
2195	2360	Lime-Shale	
2360	3340	Shale-Lime	
3340	3705	Lime-Shale	
3705	3866	Shale-Lime	Ran 140 jts of 10 1/2# 4 1/2" csg
3866	3880	Lime-Shale	Cemented w/20 bbl Salt Flush
3880	3980	Shale-Lime	200 sks 50/50 Posmix 18% Salt
3980	4500	Lime	w/3/4 of 1% CFR-2
4500	4520	Lime-Chert	PD @ 7:45 p.m. 12-9-76
4520	4525	Lime	
	4525 - TD		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well log is true and correct to the best of my knowledge and belief and according to the records of this office.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 12 1979

CONSERVATION DIVISION
 Wichita, Kansas

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 15th day of December, 1976.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

