

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kiowa SEC. 3 TWP. 27s RGE. 16 E/W  
Location as in quarters or footage from lines:  
NW NW NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Beren Corporation  
Lease Name Laura "A" #1 Well No. \_\_\_\_\_  
Office Address 970 Fourth Financial Center, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 2/5/83  
Plugging completed 2/14/83  
Reason for abandonment of well or producing formation \_\_\_\_\_

\_\_\_\_\_ Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4627'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	409'	none
				5 1/2"	4624'	3029'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 35 sacks 50/50 pos. & 1 hull, to 4400'. Shot well at  
3217' & 3029'. Pulled total of 72 joints. Plugged well with 3 sacks hulls,  
15 gel, 70 sacks cement, 10 gel, 1 hull, released plug, & 100 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing PULLING

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of FEBRUARY, 19 83

My Commission expires:



RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.  
FEB 22 1983

CONSERVATION DIVISION  
Wichita, Kansas

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - LAURA "A" #1  
Located: 330' FNL and 330' FWL of NE/4, Section 3-27S-16W,  
Kiowa County, Kansas

OWNER: Beren Corporation  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 23, 1980  
COMPLETED: December 2, 1980

TOTAL DEPTH: 4625'

LOG

0 - 1725 Shale  
1725 - 4527 Lime and Shale  
4527 - 4559 Lime  
4559 - 4625 Lime and Shale

CASING RECORD

Ran 10 joints 8 5/8" casing. 394.64'  
set at 407' K.B. Cemented with 200  
sacks Light and 100 sacks 60/40 Pozmix  
with 3% cc. Plug down at 7:15 PM,  
11-23-80, by Howco.

Ran 109 joints 5 1/2" OD new seamless  
casing. 4633' pipe set at 4624' K.B.  
Cemented with 250 sacks 60/40 Pozmix,  
10% salt, 10# gilsonite per sack, 3/4  
of 1% CFR-2. Plug down at 5:45 AM,  
12-2-80, by Howco.

RECEIVED  
STATE COOPERATION COMMISSION

DEC 6 1982

CONSERVATION DIVISION  
Wichita, Kansas

Deviation Surveys: 1° at 2170'  
1° at 4625'