

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Kingman County, Sec. 14 Twp. 27 Rge. 10 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE SW NW

Lease Owner Lawrence Supply Co., Inc.

Lease Name McMichael #2 Well No.

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 1-13-59 19

Plugging completed 1-22-59 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hample

Producing formation Depth to top Bottom Total Depth of Well 4275 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	222'	none
				5-1/2"	4274'	3636'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 4275' and found it open.  
Filled w/sand to 4265' and dumped 5 sacks of cement with dump bailer. Pulled 67 jts of 5 1/2" casing and pumped in 30 sacks of gel mud. Pulled rest of casing, cleared hole and checked fluid to 60'. Bailed hole to 200', set 10' rock bridge to 190' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1959  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel J. Knight*  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 59

My commission expires 9-27-62

*Thomas V. Pappas*  
Notary Public.

PLUGGING  
FILE SEC 14 T 27 R 10W  
BOOK PAGE 6 LINE 38

WELL LOG BUREAU—KANSAS GEOLOGICAL SURVEY  
508 East Murdock, Wichita, Kansas


31

Company- BARNETT & FOREMAN DRILLING CO.  
Farm- McMichael No. 2

SEC. 14 T. 27 R. 10W  
C S/2 S/2 NW

Total Depth. 4275½  
Comm. 9-16-54 Comp. 10-9-54  
Shot or Treated.  
Contractor.  
Issued. 11-20-54

County Kingman  
KANSAS



Elevation. 1746 RB

Production. 110 BO / 30% wtr.

CASING:

8 5/8" 222' com. w/275 sx  
5 1/2" 4274½ com. w/100 sx

Figures indicate Bottom of Formations

sand	185
redbed & shale	222
redbed	435
redbed & shale	702
Anhydrite	730
shale & shells	990
salt & shale	1295
shale & shells	1625
lime	1825
lime & shale strks	1935
lime & shale	2965
lime	3035
lime & shale	3160
lime	3250
lime & shale	3563
lime	4000
chert	4031
lime & shale	4065
shale & lime strks	4130
shale & chert	4140
lime & shale	4260
lime	4274
Viola	4275 RTD
Viola	4275½
Total depth	

Tops:	
Cimmaron Anhydrite	702
Miss. chert	4002
Kinderhook shale	4074
Kind. dolomite	4207
Viola	4274

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 14 T. 27 R. 10W  
BOOK PAGE 6 LINE 38