

15-095-19105-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kingman County, Sec. 14 Twp. 27 Rge. 10 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner Lawrence Supply Co., Inc.
Lease Name McMichael #1 Well No.
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-13-59 19
Plugging completed 1-17-59 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Depth to top Bottom Total Depth of Well 4281 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	none
				5-1/2"	4278'	3626'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 4280' and found it open.
Filled w/sand to 4270' and dumped 5 sacks of
cement with bailer. Pulled 50 jts of 5 1/2" cas-
ing and circulated pipe with 30 sacks of gel
mud. Pulled rest of casing (61 jts), cleared
hole and check fluid to 60'. Bailed hole to
200' set rock bridge to 190' and ran 20 sacks
of cement. Mudded the hole to 35', set
rock bridge to 30' and ran 10 sacks of cement
to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 1959

9-27-62

Thomas J. Dwyer
Notary Public.

My commission expires



PLUGGING
FILE SEC. 14 T. 27 R. 10W
BOOK PAGE 6 LINE 37


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BENNETT & ROBERTS DRILLING CO.
Farm. McMichael No. 1

SEC. 14 T. 27 R. 10W
C S/2 SW NW

Total Depth. 4281.5
Comm. 8-31-54 Comp. 9-19-54
Shot or Treated.
Contractor.
Issued. 11-6-54

County Kingman
KANSAS



Elevation. 1755

Production. 60 BO, 30% water

Figures indicate Bottom of Formations.

sand	180
red bed	675
anhydrite	710
shale & shells	1375
lime & shale	1511
lime	1895
lime & shale	2170
shale	2310
lime & shale	2600
shale & lime streaks	2750
lime & shale	3280
lime	3325
lime & shale	3480
lime	4045
cherty lime & shale streaks	4085
lime & shale	4270
lime	4279.5
dolomite & chert	4281.5
Total Depth	

TOPS:	
Cimarron anhydrite	675
Mississippi lime	4004
Mississippi chert	4014
Kinderhook shale	4078
Kinderhook dolomite	4209
Viola	4278

RECEIVED
STATE CORPORATION COMMISSION

DEC 31 1950

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 14 T. 27 R. 10W
BOOK PAGE 6 LINE 37