

KANSAS

TP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Messman-Rinehart Oil Co.

Complete Address 1432 Wichita Plaza Wichita, Ks

Lease Name Park Well No. 1

Location NW/SE/SW Sec. 14 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 4532

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 10:00 AM Day 22nd Month 12 Year 1971

The above well was plugged as follows:
792 ft 8 5/8 surface pipe cement circulated. 4000 ft 5 1/2 long string
cemented with 140 sacks. Top perf. 3863 ft. Sand back to 3850 ft,
5 sacks cement with bailer. Pulled 2910 ft 5 1/2. Set 20 ft rock bridge
at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *D. Russell Bihunter*
Well Plugging Supervisor

INVOICED

DATE 1-10-72

INV. NO. 4908-W