

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

15-095-00196-0001

API Number 15 - - (0W60) (of this well)

Operator's Full Name Westmore Drlg. Co., Inc. et al

Complete Address Chapin Bldg., Medicine Lodge, Ks. 67104

Lease Name Dyche Well No. 1

Location NW SE NE Sec. 14 Twp. 27S Rge. 10 (E) (W) X

County Kingman Total Depth 2613

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 4 Pm. Day 1 Month 8 Year 1979

The above well was plugged as follows:

296' 8 5/8" casing. 4 1/2" casing set at 2595' w/150 sax cement. Plug  
back to 2565'-Pref., at 2393' to 2398'-Sand back to 2350'- Top sand  
w/4 sax mixed cement w/ dump bailer-Pull 1305' 4 1/2' casing. Allied  
mixed & pumped 8 sax hulls-20 sax gel-release plug-mixed & pumped 90  
sax 50/50 posmix cement w/4% gel & 3% cc in 8 5/8" casing to top of  
casing. Shut in w/300# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

8-3-79 AUG - 3 1979

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 8.3.79  
INV. NO. 0136-W