

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20904

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Picknell Drilling Co.

Complete Address Litwin Bldg. Suite 205 Wichita Kansas 67202

Lease Name Sparbe Well No. C-1

Location C-1/2 SE-SE Sec. 8 Twp. 27 Rge. 17 (East) (West)

County Kiowa Total Depth 4732'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Picknell Drilling Co.

Address Litwin Bldg. Suite 205, Wichita Kans License No. 28 #5123

Operation Completed: Hour: 8:30 PM Day: 27 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

Anhydrites was topped at 1075' 1-st. plug @ 995' w/50
shy cent. 2nd plug @ 420' w/40 shy cent. 3rd plug on solid
bridge @ 40' to 0' w/10 shy cent. Circulated 10 shy cent.
in 4 at hole. If farmer doesn't sign release for
water well they will plug w/ 3 shy cent. The cement
was pumped through drill pipe with hole full of
heavy mud. The plugging was accomplished by
Allied cementing.

Amount of Surface Casing: 8 5/8" @ 369' cent circ. w/275 shs concrete 2% gel 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

OCT 01 1982

Signed: _____
Conservation Division Agent
Wichita, Kansas

INVOICED

DATE 10-20-82

INV. NO. 1440-W