

*10*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 11 1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bowers Drilling Co., Inc.

Complete Address: Union Center Bldg., Wichita, Kansas

Lease Name Pyle Well No. # 1

Location NW SE SE Sec. 10 Twp. 27 Rge. 16 (E) (W) W

County Kiowa Total Depth 4695

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Co.

Address: P.O. Box. 304, Chase, Kansas License No. 436

Operation Completed: Hour 2:PM Day 8th Month Feb. Year 1963

The Above well was plugged as follows:

4677' of 4 1/2" long string. Plugged back to 4542'. Top of perforation 4537'.  
Sanded to 4530' cemented with 3 sacks. 370' of 8 5/8" surface pipe cir-  
culated with cement. Hole was filled to 200' with mud, 10' rock bridge  
was set and cemented with 20 sacks. Hole filled to 40' with mud, 10'  
rock bridge was set and cemented with 10 sacks to base of cellar.  
3995' of 4 1/2" pipe recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 2/11/63

INV. NO. 6562-W