

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - (of this well)

Operator's Full Name J. Mark Richardson.

Complete Address 640 Century Plaza Bldg., Wichita, Ks. 67202

Lease Name Baker Well No. 2

Location SE NW Sec. 4 Twp. 27s Rge. 16 (E) (W) X

County Kiowa Total Depth 4550

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 2:45 PM Day 16 Month 6 Year 1980

The Above well was plugged as follows:

482' 8 5/8" casing w/400 sax cement. 4 1/2" casing set at 4549' w/150 sax
cement. Pref's at 4543-49+4490-96'-Sand back to 4450'-Top sand w/4 sax
mixed cement w/dump bailer-Pull 2800' casing-Howco mixed & pumped in
8 5/8" casing 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement w/4%
gel to top of casing. Shut in w/200# pressure.

6-23-80 JUN 23 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well-Plugging Supervisor

INVOICED

DATE 6-24-80
INV. NO. 2438-W

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Baker #2
 C-SE-NW Sec 4-27S-16W
 Kiowa County Kansas

Commenced: 6-7-77
 Completed: 6-18-77

OPERATOR: J. MARK RICHARDSON

Depth		Formation	Remarks
From	to		
0	250	Sand	Ran 12 jts of 28# 8 5/8" csg
250	490	Redbed	set @ 482' Cemented w/
490	1050	Shale-Shells	450 sks Common 3% CC
1050	1765	Shale	2% Gel PD @ 6:20 P.M.
1765	2188	Shale-Lime	6-7-77
2188	3950	Lime-Shale	
3950	4550	Lime	
	4550 - TD		Ran 142 jts of 10 1/2# 4 1/2" csg set @ 4549' Cemented w/20 bbl Salt Flush 150 sks 50/50 Posmix 18T Salt 3/4 of 1% CFR-2 PD @ 6:00 p.m. 6-18-77

STATE OF KANSAS)
) SS)
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 23rd day of June, 1977.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979

