

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name J. Mark Richardson.

Complete Address 200 O.W.Garvey Bldg., Wichita, Ks. 67202

Lease Name French "B" Well No. 1

Location NW NE SW Sec. 4 Twp. 27 Rge. 16 (E) (W) X

County Kiowa Total Depth 4525

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:45 Am. Day 8 Month 1 Year 1980

The above well was plugged as follows:

475' 8 5/8" casing w/400 sax cement. 4 1/2" casing set at 4515' w/200
sax cement. (Open hole) Sand back to 4475' - Top sand w/4 sax mixed cement
w/dump bailer. Pull 3420' 4 1/2" casing - Howco mixed & pumped 8 sax hulls
25 sax gel - 150 sax 50/50 posmix cement w/4% gel & 3% cc to top of
casing. Shut in w/300# pressure.

RECEIVED
STATE CORPORATION COMMISSION

1-10-80 JAN 10 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 1-10-80
INV. NO. 1291-W