

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1977 11-21-77
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

Operator's Full Name Imperial Oil Co.
Complete Address Box 784, Gt. Bend, Kans. 67530
Lease Name Long Well No. 1-3
Location C-19-SE Sec. 3 Twp. 27^S Rge. 16 (E) (W) X
County Seiwa Total Depth 4530

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Delco Casing Pulling
Address Box 176, Chase, Kans. 67524 License No. 683

Operation Completed: Hour 11:15 am Day 19 Month Nov Year 1977

The above well was plugged as follows:

366' 8 5/8" casing w/ 275 sac cement - 4 1/2" casing @ 4517' w/
225 sac cement - 13' open hole sand back to 4475' mix
& dump 4 sac cement w/ dump bailer - Run 3410' 4 1/2"
Casing - mix & pump 3 sac hulls 20 gal release
plug - mix & pump 125 sac 50/50 pres. 29.5 29 cc to top
of casing - shut in w/ 100# press.
Pumped by
Sun Cementing Co. Gt. Bend, Kans. 67530

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11-22-77
INV. NO. 6236-W