

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,810-0000 *h*

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Boren Corporation

Complete Address 970 Fourth Financial Center, Wichita, Kans 67202

Lease Name Valentine Ballantyne Well No. 2

Location SE-NE-NE Sec. 1 Twp. 27 Rge. 16W (East) (West)

County Kiowa Total Depth 4665'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sterling Drilling Co.

Address ^{Box} 129 - Sterling Kansas 67579 License No. _____

Operation Completed: Hour: 12:00 AM Day: 16 Month: October Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There is 452' of 8 5/8" surface casing cement circulated with 300 lbs cement. Taped anhydrite at 1070'. 1st plug at 800' with 40 lbs cement after circulating heavy mud for 10 min. 2nd plug pushed rubber plug to 425' and put 35 lbs on top of rubber plug. 3rd plug 40' to 0' on solid bridge with 10 lbs cement. Then put 5 lbs of cement in rat hole & 5 lbs cement in mouse hole. There water well was 60' deep so plugged it with 5 lbs cement pumped to bottom. They used 50/50 pause cement with 4% Jell

Plugging accomplished by Haliburton Co. out of Pratt, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-19-81

OCT 19 1981
10-19-81

Signed: Paul Luthi
Conservation Division Agent

WV. NO. 8313-W

CONSERVATION DIVISION
Wichita Kansas