

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued April 13, 1967.RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1967
6-12-67
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Skelly Oil CompanyComplete Address: P. O. Box 649, McCook, Nebraska 69001Lease Name Cunningham "B" Unit Well No. # 13Location App. C W/2 NW NE Sec. 25 Twp. 27 Rge. 11 (E) (W)WCounty Pratt Total Depth 3505'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 10:30AM Day 7th Month June Year 1967

The Above well was plugged as follows:

375' of 8 5/8" surface pipe, cemented with 150 sacks. 3446' of 5 1/2" long string,
cemented with 225 sacks. This is an open hole. Bottom of the hole was sanded to
3400', and cemented with 20 sacks, through the dump bailer. 1698' of 5 1/2" long
string was recovered from the hole. Bridge plug was pushed in fluid to 300',
bridge plug and rock bridge from 300' to 290'. 10 sacks of cement was mixed in
a barrel, and put on plug at 290', through the dump bailer, and let set over-
night. Next day hole was bailed dry, and 10 sacks of cement was added to the
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cem-
ented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 6/12/67INV. NO. 5373-W