

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1967

6-21-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued April 13, 1967.

Operator's Full Name Skelly Oil Company

Complete Address P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 15

Location App. SE NE NE Sec. 25 Twp. 27 Rge. 11 (E) W

County Pratt Total Depth 3470'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Comstock Pipe Pulling, Inc.

Address Stafford, Kansas License No. 490

Operation Completed: Hour 10:30 A.M. Day 20th Month June Year 1967

The above well was plugged as follows:

320' of 12 1/2" surface pipe, cemented with 300 sacks., 3422' of 7" long string
, cemented with 500 sacks. This is an open hole. Bottom of the hole was sanded
to 3400', and cemented with 20 sacks, through the dump bailer. 1593' of 7"
long string was recovered from the hole. Bridge plug was pushed in fluid to
275', bridge plug and rock bridge from 275' to 265'. 20 sacks of cement was
mixed in a barrel, and put on plug at 265', through the dump bailer, and let
set over-night. Next day hole was bailed dry, and 20 sacks of cement was added
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 6/21/67

INV. NO. 5435-W