

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1967
6-16-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 20

Location App. S/2 S/2 NE Sec. 25 Twp. 27 Rge. 11 (E) (W)W

County Pratt Total Depth 3466'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 5:00PM Day 12th Month June Year 1967

The Above well was plugged as follows:

365' of 10 3/4" surface pipe, cemented with 200 sacks. 3411' of 5 1/2" long string
cemented with 400 sacks. This is an open hole. Bottom of the hole was sanded
to 3400', and cemented with 20 sacks, through the dump bailer. 1698' of 5 1/2"
long string was recovered from the hole. Bridge plug was plug was pushed in
fluid to 300', bridge plug and rock bridge from 300' to 290'. 30 sacks of cem-
ent was mixed in a barrel, and put on plug at 290', through the dump bailer.

Surface pipe was swagged in, and put under water pressure, and let set over
week-end. Hole was bailed dry, and 10 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with
15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 6-16-67

INV. NO. 5415-W