

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasWell Plugging Authority,  
issued April 13, 1967.

6-7-67

RECEIVED  
JUN 7 1967  
KANSAS STATE CORPORATION COMMISSION  
Conservation Division

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 23

Location SE SE NW Sec. 25 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 3457'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 9:00AM Day 6th Month June Year 1967

The Above well was plugged as follows:

306' of 12½" Surface pipe, cemented with 300 sacks. 3417' of 6 5/8" long string, cemented with 500 sacks. This is an open hole. Bottom of the hole was sanded to 3400', and cemented with 20 sacks, through the dump bailer. 1403' of 6 5/8" long string was recoeved from the hole. Bridge plug was pushed in fluid to 275', bridge plug and rock bridge from 275' to 265'. 10 sacks of cement and 2% Calcium Chloride was mixed in a barrel, and put on plug at 265' through the dump bailer, and let set over-night. Cement failed to set. Hole was squeezed. 275 sacks of cement was pumped into a 12½" swage, to a pressure of 200 lbs., bringing the cement to the base of the cellar. This cementing was done by Halliburton Cmenting Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging SupervisorDATE 6/7/67INV. NO. 5354-W