

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-097-20697-0000 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Beren Corporation OPERATORS LICENSE NO. 5364

ADDRESS 970 4th Finan. Ctr., Wichita, Ks. 67202 PHONE # (316) 265-3311

LEASE (FARM) Kelton #1 WELL NO. _____ WELL LOCATION C NE NW COUNTY Kiowa

SEC. 12 TWP. 27s RGE. 16w (S) or (W) TOTAL DEPTH 4575' PLUG BACK TD _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 446' CEMENTED WITH 300 SACKS
CASING SIZE 5 1/2" SET AT 4574' CEMENTED WITH 250 SACKS
PERFORATED AT 4486-94', 4510-20'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK RECEIVED _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Will plug according to rules & regulations of State of Kansas. 7-5-85

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No N/A IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ted Crawford PHONE # (913) 628-6101

ADDRESS Hays, Ks. 67601

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, Ks. 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: July 3, 1985

①

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
LITH R. HENLEY
LUDITH A. McCONNELL
SIÂN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

AUG 9 1985

EXPIRES

July 9, 1985

WELL PLUGGING NOTICE

Kelton #1
C NE NW
Sec. 12-27S-16W
Kiowa County

Beren Corporation
970 4th Financial Ctr.
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).

DAILY DRILLING REPORT

PROSPECT Emma YEAR 1979 300' NW of
 WELL NO. 1 WELL LOCATION NE NW COUNTY Kiowa STATE KS
 ALL SITE LEASE DESCRIPTION Sec. 12-27S-16W CODE _____
 OPERATOR Beren Corporation ELEVATION: GR 2073
 CONTRACTOR Sterling Drilling Company DF 2080
 GEOLOGIST Bob Lewellyn KB 2083
 DEVELOPMENT WELL X PROSPECT TEST WELL _____
 OWNERSHIP 50% 1979 Beren Program
(25% Mobil, 25% Pappageorge)
 IDENTIFICATION Development Well
 NOTIFY Diane Stevens
Mobil Oil Corporation
P.O. Box 5444
Denver, Colorado 80217
(303) 572-2153

SPS: Heebner 3844 (-1761)
 BL 3994 (-1911)
 Lansing 4011 (-1928)
 BKC 4314 (-2231)
 Pawnee 4404 (-2321)
 Fort Scott 4478 (-2395)
 Cher Sd 4486 (-2403)
 Miss Chert 4503 (-2420)
 Kind Sd 4556 (-2473)

Cliff Van Horn,
 Bell Brothers
 P.O. Box 581
 Robinson, Illinois 62454
 (618) 544-2157

MOVING IN & RIGGING UP November 24, 1980 SPUD November 24, 1980

SET 8-5/8 @ 446' KB w/ 300 sx 60-40 pozmix, 2% gel, 3% CC. P.D. 8:30 PM 11-24-80.
Good returns.

DATE	DEPTH	DST
11/25/80	730'	#1 4458 - 4500 (Ch Sd) 30/45/90/90 Strong blow - GTS 40 min
11/26/80	2550'	Ga: 14,300 CFG 1/2" 50 min 15,700 CFG & stable 60 min.
11/27/80	S.D. for Thanksgiving.	Rec: 120' GCM 1012/1345 54/32 54/54
11/28/80	3188'	
11/29/80	4060'	#2 4506 - 4524 (Miss) 30/45/90/90 Strong blow, GTS 12 min.
11/30/80	4500'	Ga: 22.9 MCF, 20 min, 1/2" choke 25.0 MCF, 30 min, 1/2" choke 27.0 MCF, 40 min, 1/2" choke 27.0 MCF, 50 min, 1/2" choke 27.0 MCF, 60 min, 1/2" choke 27.0 MCF, 70 min, 1/2" choke 26.1 MCF, 80 min, 1/2" choke 26.1 MCF, 90 min, 1/2" choke 25.0 MCF, 100 min, 1/2" choke 25.0 MCF, 110 min, 1/2" choke 23.9 MCF, 120 min, 1/2" choke
12/1/80	4524'	
12/2/80	4575' RTD	Rec: 120' GCM 1259/1226 54/64 54/64
Running Great Guns Logs. Setting 5 1/2" production casing at 4574', one foot off bottom.		
LOG TOPS:		
Heebner 3840 (-1757)	Miss 4507 (-2424)	
BL 3994 (-1911)	KK Sh 4556 (-2473)	
Lansing 4013 (-1930)	KK Sd 4561 (-2478)	
BKC 4310 (-2227)	LTD 4576 (-2493)	
Pawnee 4401 (-2318)		#3 4559 - 4575 (Kind Sd) 30/30/30/30 Weak blow 10 minutes Rec: 62' mud 64/64 43/32 43/43
Fort Scott 4475 (-2392)		
Cher Sh 4481 (-2398)		
Cher Sd 4485 (-2402) (10' cIn)		

RECEIVED
 STATE CORPORATION COMMISSION

NOV 05 1985

CONSERVATION DIVISION
 Topeka, Kansas