

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 207  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-151-19005-0000

LEASE NAME Cunningham B

WELL NUMBER 43

720 Ft. from S Section Line

1332 Ft. from E Section Line

SEC. 25 TWP. 27 RGE. 11 (E) or (W)

COUNTY Pratt

Date Well Completed 4/30

Plugging Commenced 6/08/00

Plugging Completed 6/08/00

RECEIVED  
 JUN 26 2000  
 STATE CORPORATION COMMISSION

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

CONSERVATION DIVISION  
 Wichita, Kansas

LEASE OPERATOR K.C. Resources, Inc.

ADDRESS P. O. Box 1118, Cardiff, CA 92007

PHONE: 760-753-3330 OPERATORS LICENSE NO. 3880

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/07/00 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached?           

Producing Formation K.C. Lansing Depth to Top 3408 Bottom 3750 T.D. 4018'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
K.C. Lansing	Oil	Surface	395	10 3/4"	395'	None
3408-3750		Surface	4018	5 1/2"	4018'	None
Viola	Oil					
3998-4018						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set:

Well was plugged back to 1600' in 1994 and perforated in chase zone. Ran in and set CIBP at 1400' and put a 2-sack cement plug on top. Shot squeeze holes at 400' but could not pump into holes, max pressure at 500 psi, ran in 620' of tubing and pumped a 80 sack cement plug to surface.

Name of Plugging Contractor Pratt Well Service / United Cementers License No.           

Address Pratt Well Service, Pratt, KS; United Cementers, El Dorado, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: K. C. Resources, Inc.

STATE OF California COUNTY OF San Diego, ss.

Kenneth Wayne Gibson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 1190 Encinitas Blvd 1276, Enc. CA 92024

SUBSCRIBED AND SWORN TO before me this 21 day of June, 192000

[Signature]  
 Notary Public

My Commission Expires: Dec 5, 2003



Form CP-4  
 Revised 05-88

[Handwritten Mark]