


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 14 Twp. 27S Rge. 11 (E) (W)
Location as "NE/CNW/SW" or footage from lines Center of W_{1/2}-NE SE
Lease Owner Gordon Morian C/O Acid Engineers
Lease Name Crick Well No. 1
Office Address 630 United Founders Tower Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 8-30-66 Renewal Date _____ 19____
Application for plugging approved 8-31-66 _____ 19____
Plugging commenced 3-26-66 _____ 19____
Plugging completed 9-3-66 _____ 19____
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	307	None
				5 1/2	None	3155

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 3800'. Dumped 5 sacks of cement. Working pipe.

Working pipe. Had 19" stretch at 30 joints. Ran weight to clear hole for shot and fluid. Found fluid at 1400'. Shot pipe at 3313'. Working pipe.

Working pipe. Pulling pipe.

Ran Halliburton weight. Checked collars and bottom. Cleaned out cellar. Found bridge at 290' - filled with crushed rock to 260'. Made up bailer. Mixed and dumped 10 sacks of cement on bridge at 260' - let set overnight.

Bailed down hole. Dumped 20 sacks on overnight bridge. Mudded hole to 40' - set 10' rock bridge. Capped well with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of September, 19 66

My commission expires May 27, 1969

Notary Public.

WELL LOG

COMPANY GORDON MORAIN

SEC. 14 T. 27S R. 11W

FARM CRICK

NO. 1

LOC. C-W/2, NE, SE

TOTAL DEPTH 3860'

COUNTY PRATT CO., KANSAS

COMM. August 5, 1961


COMP. August 15, 1961

CONTRACTOR

GARVEY DRILLING COMPANY

CASING

8-5/8" @ 307' w/200 sax.
5 1/2" @ 3853' w/75 sax.



ELEVATION 1805' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

115	Red bed & shale
130	Sand
375	Red bed & shale
1165	Red bed, shale & shells
1600	Shale
1735	Shale & lime
1995	Lime
2140	Lime & shale
2310	Lime
2590	Shale & lime
2965	Lime & shale
3407	Lime
3643	Shale & lime
3860	Lime
3860	T. D.

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS

County of BARTON

I, VERNE A. MORRIS

of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 CRICK well.

Subscribed and sworn to before me this 22nd day of August 1961

My Commission Expires November 12, 1962

Verne A. Morris
NOTARY PUBLIC