

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

A blank 4x4 grid of squares, intended for drawing a square and its diagonals.

**Locate well correctly on above
Section Plat**

Pratt	County, Sec. 14	Twp. 27	Rge. (E) 11	(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 990' N. & 990' W. of S $\frac{1}{4}$ Cor.				
Lease Owner Cities Service Oil Co. et al.				
Lease Name Park		Well No. 1		
Office Address Bartlesville, Oklahoma				
Character of Well (completed as Oil, Gas or Dry Hole)		Dry Hole		
Date well completed		July 29	19	49
Application for plugging filed		July 29	19	49
Application for plugging approved		July 29	19	49
Plugging commenced		July 29	19	49
Plugging completed		July 29	19	49
Reason for abandonment of well or producing formation		Dry Hole		

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well.....Ruel Durkee.....
Producing formation.....Arbuckle..... Depth to top.....4478'..... Bottom.....4532'..... Total Depth of Well.....4532..... Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

4532' to 300' heavy mud.
300' to 250' wood plug and 15 sacks cement.
250' to 20' mud.
20' to base of cellar, 5 sacks cement.

8-23-49 AUG 23 1949

STATE OF KANSAS
COMMISSIONER OF
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... R. C. Cooper
Address..... Box 751
..... Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or ~~(owner or operator)~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Tom Connor

Box 751, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 77th day of August 1949

My commission expires March 12, 1951.

Notary Public.



WELL RECORD

Cities Service Oil Co.
 Company..... et. al. Well No. 1 Farm Park
 Location..... 990' North and 990' West of S/4 Corner Sec. 14 T. 27 R. 11W
 Elevation..... 1808 (1805 Gr.) County..... Pratt State..... Kansas
 Drlg. Comm. July 13, 1949 Contractor..... R. W. Fine Drilling Company
 Drlg. Comp. July 29, 1949 Acid..... None
 T. D. 4532' Initial Prod. None - Dry Hole. P. & A. 7-29-49.

CASING RECORD:

8-5/8" @ 795' cem. 400 mx cement
 and 400# C. C.

FORMATION RECORD:

clay & sand	0-245
red bed & shale	500
red bed, shale & shells	700
shale & shells	795
red bed & shale	1265
shale	1385
salt	1550
shale & shells	1720
lime & shale	2090
shale	2255
lime & shale	2745
shale	2780
lime & shale	2995
shale & lime	3140
lime	3330
lime & shale	3550
lime	3615
lime & chalk	3620
lime	4086
cherty lime	4143
lime	4180
shale & pyrite	4210
lime & shale	4265
lime, chert & shale	4304
lime	4520
lime & sand	4532 T. D.

Top Lansing	3620'
Top Mississippi	4082'
Top Kinderhook	4192'
Top Viola	4313'
Top Simpson	4398'
Top Arbuckle	4478' ✓
Penetration	54'
Total Depth	4532'

SYFO:	500'	1°
	1000'	0°
	1500'	0°
	2000'	2°
	2500'	1°
	3000'	1°
	3500'	1°
	4000'	0°
	4400'	0°

RECEIVED

Conservation Div.

AUG 23 1949

STATE CORPORATION

