


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

**WELL PLUGGING RECORD**



Kingman County, Sec. 14 Twp. 27 Rge. (E) 10 (W)  
Location as "NE/CNW/SW" or footage from lines NW - SE - NE  
Lease Owner Morganstern & Spector, Inc.  
Lease Name Cannon Well No. 2  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 8-19-51 19  
Application for plugging filed Nov. 10, 1959 19  
Application for plugging approved Nov. 12, 1959 19  
Plugging commenced 12-2 19 59  
Plugging completed 12-5 19 59  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Viola Depth to top 4275 Bottom 4277 Total Depth of Well 4277 Feet  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	296	None
				5 1/2	4276	3016.08

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 4000' - dumped 5 sacks of cement - mudded to 250' - set 10' rock bridge - dumped 20 sacks of cement - mudded to 30' - set rock bridge - dumped 10 sacks of cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 19 1960  
1-19-60  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company License # 236  
Address Box 154 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morganstern*

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1959

My commission expires Dec 1, 1963

*Elzie Carby*  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murtzock, Wichita, Kansas


Company: LION OIL CO.  
Farm: Cannon No. 2

SEC. 14 T. 27 R. 10W  
NW SE NE

00000

Total Depth. 4277  
Comm. 8-7-51 Comp. 8-19-51  
Shot or Treated.  
Contractor. The R. W. Rine Drlg. Co.  
Issued. 11-3-51

County Kingman  
KANSAS



CASING:  
8 5/8" 296' cem. w/250 sx  
5 1/2" 4276' cem. w/200 sx

Elevation. 1750

Production. 285 BO & 5% wtr. pot

Figures Indicate Bottom of Formations.

sand & surface	300
red bed & shale	770
shale & shells	1330
lime & shale	2285
shale	2610
lime & shale	3575
lime	3645
lime & shale	3738
lime	4000
lime & shale	4015
chert & lime	4066
lime	4120
shale	4240
lime & shale	4277
Total Depth	

Tops:	
Lansing	3495
Miss.	4010
Viola	4275

Acidized w/1000 gals.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 11 1959

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1/14/60

INV. NO. 705-w