

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Kingman County, Sec. 14 Twp. 27 Rge. (E) 10 (W)

Location as "NE/CNW&SW" or footage from lines CE/2-SW - SE

Lease Owner Morganstern & Spector, Inc.

Lease Name Cannon Well No. 4

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 10-13-51 19

Application for plugging filed Nov. 10, 1959 19

Application for plugging approved Nov. 12, 1959 19

Plugging commenced 12-7 19 59

Plugging completed 12-9-59

Reason for abandonment of well or producing formation failure to produce


profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Viola Depth to top 4262 Bottom 4263 Total Depth of Well 4264 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8	290	None
				5 1/2	4263	3141.44

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 4250' - dumped 5 sacks of cement - bailed off oil - mudded to 250' - set 10' rock bridge - dumped 20 sacks of cement - mudded to 30' - set 10' rock bridge - dumped 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236

Address Box 154 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. J. [unclear]*

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1959

(Address) Elsie Cady
Notary Public.

My commission expires Dec 1, 1963

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- LION OIL COMPANY
Farm- Cannon No. 4

SEC. 14 T. 27 R. 10W
CE/2 SW NE

Total Depth. 4264
Comm. 10-2-51 Comp. 10-13-51
Shot or Treated. Acid 500
Contractor. R. W. Rine Drlg. Co.
Issued. 1-12-52

County Kingman
KANSAS



Elevation. 1736 DF

Production. Phys. pot. pump 178
bopd / no wtr.

Figures Indicate Bottom of Formations.

sand	165
red bed, shells	295
red bed, shale	585
shale, shells	1220
shale, shell, lime	1540
lime, shale	1710
lime	1900
shale, lime	2210
shale	2965
shale, lime	3110
shale	3305
shale, lime	3565
lime	3690
lime, shale	3760
lime	4015
Miss. chert	4053
shale, lime	4065
shale	4210
lime, shale	4264
Total depth	

Tops:	
Brown Lime	3480
Lansing	3490
Miss.	4015
Kinderhook	4070
Viola	4262

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1951

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE

1/14/60

INV. NO.

698-4