


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

R

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kingman County, Sec. 14 Twp. 27 Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines SE - NW - NE
Lease Owner Morganstern & Spector, Inc.
Lease Name Cannon Well No. 3
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-6-51 19
Application for plugging filed Nov. 10, 1959 19
Application for plugging approved Nov. 12, 1959 19
Plugging commenced 11-28 19 59
Plugging completed 12-2 19 59
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Viola Depth to top 4273 Bottom 4278 Total Depth of Well 4279 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 9 5/8, 308, None. Row 2: 5 1/2, 4278, 3243.37

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 4280' to 4240' - dumped 5 sacks of cement - bailed off oil to 250' - filled with mud to 250' - set 10' rock bridge - dumped 20 sacks of cement - mudded to 30' - set rock bridge - dumped 10 sacks of cement to base of cellar.

RECEIVED STATE CORPORATION COMMISSION

JAN 19 1960

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 154 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1959

[Handwritten Signature]

Notary Public.

My commission expires Dec 1, 1963

