


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

R
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 13 Twp. 27 Rge. 10 (E) W (W)
Location as "NE/CNW&SW" or footage from lines CE/2 NW SE
Lease Owner Morgenstern & Spector
Lease Name Bick #7 Well No.
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 12-4-51 19
Application for plugging filed Nov. 10, 1959 19
Application for plugging approved Nov. 12, 1959 19
Plugging commenced 12-12-59 19
Plugging completed 12-14-59 19
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation Viola Depth to top 4265 Bottom 4265 1/2 Total Depth of Well 4267 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8" OD	289'	none
				5-1/2"		3215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4267' and found it open.
Filled w/sand to 4240' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.
Cleared hole and mudded the hole to 220', set 10' rock bridge and dumped 20 sacks of cement.
Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETEED

RECEIVED
STATE CORPORATION COMMISSION

1-19-60 JAN 19 1960

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1959

Thomas V. Duggan
Notary Public.

My commission expires 9-27-62



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East McDock, Wichita, Kansas


COPY

Company- LION OIL CO.
Farm- Bick No. 7

SEC. 14 T. 27 R. 18W
OE/2 NW SE

Total Depth. 4267
Comm. 11-22-51 Comp. 12-4-51
Shot or Treated.
Contractor. The R. W. Rine Drlg. Co.
Issued. 3-8-52

County Kingman
KANSAS



Elevation. 1727

Production. Pmp. 127 BOPD NW

Figures Indicate Bottom of Formations.

sand	150
red bed	295
red bed, shale, shells	850
shale & salt	1365
lime	1420
lime & shale	1690
lime	2130
shale & lime	2525
shale	2810
shale & lime	3014
shale	3155
lime & shale	3465
lime	3955
shale & lime	3998
miss.	4040
lime & shale	4250
lime	4267 RTD
Total Depth	

Tops:	
Brown Lime	3475 SJ
Lansing	3485 SJ
Miss.	3994 SJ
Viola	4262 SJ
Viola	4265 DT.

DP & CO 4267, test 1 boph natural
500 acid, swab 25 boph, POP, WOP

SJTD 4264

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1959
CON. DIVISION

INVOICED
DATE 4/14/60
INV. NO. 701-w